9900CX FACILITY PLANNER

1400/1750/2100 KVA UPS 480VIN/480VOUT 60 HZ 0.95 PF



UPS MAIN INPUT DATA				UPS BYPASS INPUT DATA		UPS OUTPUT DATA		
UPS OUTPUT	UPS	UPS INPUT	UPS INPUT	MAIN (BIN)	UPS BYPASS	UPS BYPASS	UPS OUTPUT	UPS OUTPUT
POWER	INPUT	(KVA)	CURRENT	EXTERNAL OVERCURRENT	CURRENT (NOM)	EXTERNAL OVERCURRENT	CURRENT	EXTERNAL OVERCURRENT
RATING	POWER	NOM/MAX	NOM/MAX	PROTECTION TRIP	(A)	PROTECTION TRIP	NOM/MAX	PROTECTION TRIP (NOM)
(KVA)/(KW)	(kW)		(A)	(A)		(A)	(A)	(A)
1400/1333	1374	1373/1564	1651/1881	2000 (100% Rated)	1684	2000 (100% Rated)	1684/2526	2000 (100% Rated)
1750/1666	1717	1734/1975	2085/2375	2500 (100% Rated)	2105	2500 (100% Rated)	2105/3157	2500 (100% Rated)
2100/2000	2065	2085/2374	2507/2855	3000 (100% Rated)	2526	3000 (100% Rated)	2526/3789	3000 (100% Rated)
NOTES	1,2,3,4		5	2,6,7	7	2,6,7	10,11,12	2,8

	BATTERY SYSTEM DATA		
UPS OUTPUT POWER RATING (KVA)/(KW)	BATTERY SYSTEM OUTPUT CURRENT AT 400VDC END VOLTAGE (A)	BATTERY CABINET OVERCURRENT PROTECTION TRIP (A)	
1400/1333	3457	800	
1750/1666	4321	800	
2100/2000	5208	800	
NOTES	2,9,16	2	

MECHANICAL DATA						
UPS RATING (KVA)	DIMENSIONS (W X D X H) (INCHES)	WEIGHT (LBS)	Max Elevation (FT) / Max Temperature (F)	DISTRIBUTED FLOOR LOADING (LBS/FT ²)	POINT LOADING (LBS/FT ²)	
1400	167.3 X35.5 X 80.7	9,180	6500/104	232	2,545	
1750	198.8 X 35.5 X 80.7	11,110	6500/104	241	2,545	
2100	222.4 X 35.5 X 80.7	13,530	6500/104	247	3,039	
IOTES					15	

	HEAT LOSS AND AIR FLOW				
UPS RATING (KVA)	HEAT REJECTION 100% (kBTU/Hr)	EFFICIENCY 100% LOAD (PERCENT)	AIR FLOW REQUIREMENTS (CFM)		
1400	150.0	96.8	18,210		
1750	187.5	96.8	22,760		
2100	236.6	96.6	27,310		
NOTES	13,14	4			



www.mitsubishicritical.com UPSSales@meppi.com 800-887-7830 • 724-772-2555

9900CX FACILITY PLANNER





- 1. Acceptable input and bypass voltage range is 480VAC, +15%, -20%
- 2. Install and ground the UPS system in accordance with NFPA 70 National Electrical Code and all federal, state and local regulations.
- 3. UPS main input and bypass frequency: $60Hz \pm 10\%$.
- 4. UPS input power factor: 0.99 at 100% load and 0.99 at 50% load. The UPS input power factor is independent of the UPS output (load) power factor.
- 5. The nominal current is continuous and is based on 100% load. The maximum current includes the nominal input current at 100 % load and the non-continuous battery recharge current. Consult factory before operating at the maximum current.
- 6. Power main input and bypass feeder inputs (provided by others) from separate overcurrent protection devices. Main input overcurrent protection devices are sized based on the maximum current which includes the maximum battery charging current.
- 7. Main Input and bypass input are 3-phase, 3-wire plus ground. UPS cable entry cabinet has top or bottom conduit entry.
- 8. UPS output overcurrent protection device is provided by others. UPS output cables are to be run conduits separate from the input and bypass cables: 3-phase, 3-wire plus ground.
- 9. Consult the factory when using a non-lead acid battery stored energy system.
- 10. UPS inverter output voltage regulation: ±1% balanced load, ±2% unbalanced load.
- 11. UPS output total harmonic voltage distortion (THDv): ≤2% at 100% linear load and ≤5% at 100% nonlinear load.
- 12. Maximum load crest factor: 2.3.
- 13. The specified heat losses are only for the UPS module. Peripheral equipment heat losses must be considered separately.
- 14. Maintain clearances per the UPS installation drawing. Minimum overhead clearance: 23.6 inches.
- 15. Use point loading with raised-floor installations.
- 16. Includes cable entry cabinet.



www.mitsubishicritical.com
UPSSales@meppi.com
800-887-7830 • 724-772-2555